

EOG Resources, Inc.
P.O. 1910
Vernal, UT 84078

September 5, 2003

Utah Division of Oil, Gas, & Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, UT 84114-5801


RE: APPLICATION FOR PERMIT TO DRILL
SOUTH CHAPITA 6-3
SW/NE, SEC. 3, T10S, R23E
UINTAH COUNTY, UTAH
LEASE NO.: UTU-80613
FEDERAL LANDS

Enclosed please find a copy of the Application for Permit to Drill and associated attachments for the referenced well.

Please address further communication regarding this matter (including approval) to:

Ed Trotter
P.O. Box 1910
Vernal, UT 84078
Phone: (435)789-4120
Fax: (435)789-1420

Sincerely,



Ed Trotter
Agent
EOG Resources, Inc.

Attachments

RECEIVED

SEP 19 2003

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0136

001



APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. TYPE OF WORK <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease serial No. UTU-80613	
b. TYPE OF WELL <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe name	
2. Name of Operator EOG RESOURCES, INC.		7. If Unit or CA Agreement, Name and No.	
3a. Address P.O. BOX 1910, VERNAL, UT 84078		8. Lease Name and Well No. SOUTH CHAPITA 6-3	
3b. Telephone Number: (435)789-4120		9. API Well No. 43-047-35217	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 2105' FNL & 2021' FEL 4426447 Y SW/NE 39.97957 At proposed prod. Zone 444284 X -109.31029		10. Field and pool, or Exploratory NATURAL BUTTES	
14. Distance in miles and direction from nearest town or post office* 28.25 MILES SOUTHEAST OF OURAY, UTAH		11. Sec., T., R., M., or BLK. And survey of area SEC. 3, T10S, R23E, S.L.B.&M.	
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. Unit line, if any) 2021'		12. County or parish UINTAH	13. State UTAH
16. No. of acres in lease 642		17. Spacing Unit dedicated to this well	
18. Distance from proposed location* to nearest well, drilling, completed, or applied for, on this lease, ft. See Map C		20. BLM/BIA Bond No. on file #NM 2308	
21. Elevations (show whether DF, KDB, RT, GL, etc.) 5396.8 FEET GRADED GROUND		22. Approx. date work will start* UPON APPROVAL	
23. Estimated duration RECEIVED		24. Attachments SEP 19 2003	

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan
3. A Surface Use Plan (if the location is on National Forest System lands, the SUPO shall be filed with the appropriate Forest Service Office.

4. Bond to cover the operations unless covered by an existing bond on file (see item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the Authorized officer.


25. Signature 	Name (Printed/ Typed) Ed Trotter	Date September 5, 2003
Title Agent		
Approved by (Signature) 	Name (Printed/ Typed) BRADLEY G. HILL	Date 09-25-03
Title Office ENVIRONMENTAL SCIENTIST III		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

T10S, R23E, S.L.B.&M.



LEGEND:

- = 90° SYMBOL
- = PROPOSED WELL HEAD.
- = SECTION CORNERS LOCATED.

(AUTONOMOUS NAD 27)
 LATITUDE = 39°58'46.06" (39.979461)
 LONGITUDE = 109°18'36.66" (109.310183)

EOG RESOURCES, INC.


Well location, SOUTH CHAPITA #6-3, located as shown in the SW 1/4 NE 1/4 of Section 3, T10S, R23E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

BENCHMARK 58 EAM (1965) LOCATED IN THE NE 1/4 OF SECTION 30, T9S, R23E, S.L.B.&M. TAKEN FROM THE RED WASH SE, QUADRANGLE, UTAH, UTAH COUNTY 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5132 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF

REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 07-21-03	DATE DRAWN: 07-25-03
PARTY K.K. K.G. D.COX	REFERENCES G.L.O. PLAT	
WEATHER HOT	FILE EOG RESOURCES, INC.	

EIGHT POINT PLAN

SOUTH CHAPITA 6-03
SW/NE, SEC. 3, T10S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	DEPTH (KB)
Green River	1,645'
Wasatch	4,190'
Island	6,615'
KMV Price River	6,785'
KMV Price River Middle	7,205'
KMV Price River Lower	7,775'
Bit Trip Sego	8,165'
Sego	8,225'

EST. TD: 8325

Anticipated BHP 3600 PSI

- 3. PRESSURE CONTROL EQUIPMENT:** Intermediate Hole - 3000 PSIG
Production Hole – 5000 PSIG
BOP Schematic Diagrams attached.

4. CASING PROGRAM:

<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>LENGTH</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>THREAD</u>	<u>RATING FACTOR</u>		
							<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
17 1/2"	0' - 250' +/- KB	250' +/-	13 3/8"	48.0 #	H-40	STC	770 PSI	1730 PSI	322,000#
12 1/4"	250' - 2500' +/-KB	2500 +/-	9 5/8"	36.0 #	J-55	STC	2020 PSI	3520 PSI	394,000#
7 7/8"	2500' – TD +/-KB	8325' +/-	4 1/2"	11.6 #	N-80	LTC	6350 PSI	7780 PSI	223,000#

All casing will be new or inspected.

5. Float Equipment:

Surface Hole Procedure (0-250' Below GL):

Guide Shoe
Insert Baffle
Wooden wiper plug
Centralizers: 1 – 5-10' above shoe, every collar for next 3 joints (4 total).

Intermediate Hole Procedure (250'-2500'):

Guide Shoe
Insert Float Collar (PDC drillable)
Cents.: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

EIGHT POINT PLAN

SOUTH CHAPITA 6-03 **SW/NE, SEC. 3, T10S, R23E, S.L.B.&M.** **UINTAH COUNTY, UTAH**

Float Equipment (Continued)

Production Hole Procedure (2500'-TD):

FS, 1 joint of casing, FC, and balance of casing to surface. Run 11.6#, N-80 burst rating or equivalent marker collars or short casing joints at $\pm 6,785'$ (**Top of Price River**) and $\pm 3,800'$ (**400' above the Wasatch**) (alter depth if needed to avoid placing across any potentially- productive intervals). Centralize 5' above shoe on joint #1, top of joint #2, then every 2nd joint to **400' above Island top** (50 total). Thread lock FS, top and bottom of FC, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (0-250' below GL):

Air – Air Water Mist

Intermediate Hole Procedure (250-2500'):

Water (circulate through reserve pit) with Gel/LCM sweeps.

Production Hole Procedure (2500'-TD):

2700' - 4500' Water (circulate through reserve pit) with Gel/LCM sweeps.

4500' - 6900' Close in mud system. "Mud up" with **6.0 ppb** Diammonium Phosphate (DAP). Drill with DAP water, POLYPLUS for viscosity and hole cleaning, adding KLA-GARD B for supplemental inhibition. Also sweep hole periodically w/ Durogel / LCM sweeps to clean the hole and seal loss zones. Add additional LCM as hole dictates. Mud weight and vis as needed, water loss – no control.

6900' - TD Discontinue KLA-GARD B. Utilize POLYPAC-R for fluid loss control. Maintain **5.5 ppb** DAP. **Do not mix caustic or lime.** Maintain 7.5-8.5 pH. Weight up system and add vis as hole conditions require. Run LCM sweep periodically to seal off loss zones or more often as hole dictates. Water loss: 20 cc's maximum. Expect increasing gas shows requiring heavier mud weights from top of Island onward. Treat CO₂ contamination with DESCO CF and OSIL (Oxygen scavenger) if mud properties dictate.

7. VARIANCE REQUESTS:

- A. EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line (Where possible, a straight run blooie line will be used).
- B. EOG Resources, Inc. requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line. (Not required on aerated water system).
- C. EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be 75' in length.

EIGHT POINT PLAN

SOUTH CHAPITA 6-03 **SW/NE, SEC. 3, T10S, R23E, S.L.B.&M.** **UINTAH COUNTY, UTAH**

8. EVALUATION PROGRAM:

Logs: RST (reservoir saturation tool) cased hole logs will be run from TD to surface.

9. CEMENT PROGRAM:

Surface Hole Procedure (0-250' Below GL)

Lead: 300 sks (100% excess volume) Class 'G' cement with 2% S1 (CaCl₂) & 0.25 pps D29 (cellophane flakes), mixed at 15.8 ppg, 1.16 ft³/sk., 4.95 gps water.

Top Out: Top out with Class 'G' cement with 2% S1 (CaCl₂) in mix water, 15.8 ppg, 1.16 ft³/sk., 4.95 gps via 1" tubing set at 25' if needed.

Intermediate Hole Procedure (250'-2500')

Lead: 85 sks: (50% excess volume) Class 'G' lead cement (coverage from 1700-1000') with 5% D44 (Salt), 12% D20 (Bentonite), 1% D79% (Extender), 0.25% D112 (Fluid Loss Additive), 0.2% D46 (Anti-Foamer) & 0.25 pps D29 (Cellophane flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 290 sks: (50% excess volume) Class 'G' cement (coverage from 2700-1700') with 10% D53 (Gypsum), 2% S1 (CaCl₂) & 0.25 pps D29 (Cellophane flakes) mixed at 14.2 ppg, 1.61 ft³/sk., 7.9 gps water.

Production Hole Procedure (2500' to TD)

Lead: 110 sks 35:65 Poz G w/ 4% D20 (Bentonite), 2% D174 (Extender), 0.2% D65 (Dispersant), 0.2% D46 (Antifoam), 0.75% D112 (Fluid Loss Additive), 0.15% D13 (Retarder), 0.25 pps D29 (cello flakes), mixed at 13.0 ppg, 1.73 cu. ft./sk., 9.06 gps water

Tail: 190 sks: 50:50 Poz G w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.15% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 cu. ft./sk., 5.9 gps water.

10. ABNORMAL CONDITIONS:

INTERMEDIATE HOLE (250-2500')

Potential Problems: Lost circulation below 1800' and minor amounts of gas may be present.

EIGHT POINT PLAN

SOUTH CHAPITA 6-03
SW/NE, SEC. 3, T10S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

ABNORMAL CONDITIONS (Continued):

PRODUCTION HOLE (2500'-TD)

Potential Problems: Sloughing shales and key seat development are possible in the Wasatch Formation. CO₂ contamination in the mud is possible in the Price River (Mesa Verde).

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

3000 PSIG DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 3000 PSIG RATED.
CASING FLANGE IS 11" 3000 PSIG RATED.
BOPE 11" 3000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 3000 psig.
3. Annular preventor will be tested to 50% of working pressure, 1500 psig.
4. Casing will be tested to 0.22 psi/ft. or 1500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure-tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 3000 psig BOPE specifications.




5000 PSIG DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 5000 PSIG RATED.
CASING FLANGE IS 11" 5000 PSIG RATED.
BOPE 11" 5000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 5000 psig.
3. Annular preventor will be tested to 50% of working pressure, 2500 psig.
4. Casing will be tested to 0.22 psi/ft. or 2500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure-tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 5000 psig BOPE specifications.



EOG RESOURCES, INC.
SOUTH CHAPITA #6-3
SECTION 3, T10S, R23E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN A EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 3.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN LEFT AND PROCEED IN A SOUTHELRY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 3.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN LEFT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN RIGHT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.8 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE SOUTH CHAPITA #6-3 TO THE NORTHEAST; FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE NORTHEAST; FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.15 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 59.35 MILES.

**CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL**

Company/Operator:	<u>EOG Resources, Inc.</u>
Well Name & Number:	<u>South Chapita 6-3</u>
Lease Number:	<u>UTU-80613</u>
Location:	<u>2105' FNL & 2021' FEL, SW/NE, Sec. 3,</u> <u>T10S, R23E, S.L.B.&M., Uintah County, Utah</u>
Surface Ownership:	<u>Federal</u>

NOTIFICATION REQUIREMENTS

Location Construction - forty-eight (48) hours prior to construction of location and access roads.

Location Completion - prior to moving on the drilling rig.

Spud Notice: - at least twenty-four (24) hours prior to spudding the well.

Casing String and
Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.

BOP and related
Equipment Tests - twenty-four (24) hours prior to running casing and tests.

First Production
Notice - within five (5) business days after new Well begins or production resumes after Well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

THIRTEEN POINT SURFACE USE PROGRAM

1. EXISTING ROADS

- A. See attached Wellsite Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 28.25 miles southeast of Ouray, Utah - See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary. No off lease Right-of-Way will be required.

2. PLANNED ACCESS ROAD

- A. The access road will be approximately 0.15 miles in length. See attached TOPO Map "B".
- B. The access road has a 30 foot ROW w/ 18 foot running surface.
- C. Maximum grade on access road will be 8%.
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No culverts, bridges, or major cuts and fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards, or fences will be required or encountered.

New or reconstructed roads will be centerlined - flagged at time of location staking.

The road shall be upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Upgrading shall include ditching, drainage, graveling, crowning, and capping the roadbed as necessary to provide a well-constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot Right-of-Way will not be allowed.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossings nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by run off water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

As operator, EOG Resources, Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

3. **LOCATION OF EXISTING WELLS WITHIN A ONE MILE RADIUS OF PROPOSED WELL LOCATION**

A. Producing wells - 4*

(*See attached TOPO map "C" for location)

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

A. **ON WELL PAD**

1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, 300 Bbl vertical or 200 Bbl low profile, condensate tank, and attaching piping.
2. Gas gathering lines - A 3" gathering line will be buried from dehy to the edge of the location.

B. **OFF WELL PAD**

1. Proposed location of attendant off pad flowlines shall be flagged prior to archaeological clearance.
2. A 3" OD steel above ground natural gas pipeline will be laid approximately 197' from proposed location to a point in the SW/NE of Section 3, T10S, R23E, where it will tie into Questar Pipeline Co.'s existing line. Proposed pipeline crosses Federal lands, thus a Right-of-Way grant will be required.
3. Proposed pipeline will be a 3" OD steel, welded line laid on the surface.
4. Protective measures and devices for livestock and wildlife will be taken and/or installed where required.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire contents of the largest tank within the facility/battery.

The production facilities will be placed on the Northwest side of the location.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. Facilities

required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Carlsbad Canyon.

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligation as determined by the authorized officer.

5. LOCATION & TYPE OF WATER SUPPLY

- A. Water supply will be from Ouray Municipal Water Plant at Ouray, Utah, and/or Target Trucking Inc.'s water source in the SW/SW, Sec. 35, T9S, R22E, Uintah County, Utah (State Water Right #49-1501). Produced water from the Chapita Wells and Stagecoach Units will also be used.
- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIAL

- A. All construction material for this location and access road will be of native borrow and soil accumulated during the construction of the location.
- B. All construction material will come from Federal Land.
- C. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL

A. METHODS AND LOCATION

- 1. Cuttings will be confined in the reserve pit.
- 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
- 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.
- 4. Produced wastewater will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following three locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).

5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.
- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in the reserve pit or be removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

On BLM administered land:

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with a plastic liner. A felt liner will also be installed if rock is encountered during pit construction.

8. **ANCILLARY FACILITIES**

- A. No airstrips or camps are planned for this well.

9. **WELLSITE LAYOUT**

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.
- D. The approved seed mixture for this location is:
 - Gardner Salt Bush – 4 pounds per acre
 - Indian Rice Grass – 3 pounds per acre
 - Wyoming Big Sage – 3 pounds per acre
 - Hi-Crest Crested Wheat Grass – 2 pounds per acre.

The reserve pit will be located on the South side of the location. The flare pit will be located downwind of the prevailing wind direction on the South side of the location, a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled pit topsoil will be stored separate from the location topsoil between Corners B and 5. The stockpiled location topsoil will be stored between Corners 2 and 8. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture for this location and then walked down with a cat.

Access to the well pad will be from the Southeast.

X Corner #8 will be rounded off to minimize excavation.

FENCING REQUIREMENTS:

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion of construction, the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly traveled. If the well is a producer, the cattleguards (shall/shall not) be permanently mounted on concrete bases. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RESTORATION OF SURFACE

A. PRODUCING LOCATION

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

B. DRY HOLE/ABANDONED LOCATION

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the BLM will attach the appropriate surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP

Access road: Federal

Location: Federal

12. OTHER INFORMATION

A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the AO. Within five working days the AO will inform the operator as to:

-whether the materials appear eligible for the National Register of Historic Places;

-the mitigation measures the operator will likely have to undertake before the site can be used.

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, EOG Resources, Inc. will control noxious weeds along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- C. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on BLM lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

Additional Surface Stipulations

- X No construction or drilling activities shall be conducted between April 1 and August 15 due to Burrowing Owl Stipulations.**

LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION

PERMITTING AGENT

Ed Trotter
P.O. Box 1910
Vernal, UT 84078
Telephone: (435)789-4120
Fax: (435)789-1420

DRILLING OPERATIONS

Donald Presenkowski
EOG Resources, Inc.
P.O. Box 250
Big Piney, WY 83113
Telephone: (307)276-4865

All lease or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approval plan of operations, and any applicable Notice to Lessees. EOG Resources, Inc. is fully responsible for the actions of their subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.


A copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions that presently exist; that the statements made in the Plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this Plan and the terms and conditions under which it is approved.

Please be advised that EOG Resources, Inc. is considered to be the operator of the **South Chapita 6-3 Well, located in the SW/NE of Section 3, T10S, R23E, Uintah County, Utah; Lease #UTU-80613;** and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is provided under Bond #NM 2308.

9-5-2003
Date


Agent

EOG RESOURCES, INC.

SOUTH CHAPITA #6-3

LOCATED IN UINTAH COUNTY, UTAH

SECTION 3, T10S, R23E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHEASTERLY




PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: NORTHEASTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

7 22 03
MONTH DAY YEAR

PHOTO

TAKEN BY: K.K.

DRAWN BY: K.G.


REVISED: 00-00-00

SCALE: 1" = 50'
DATE: 07-25-03
Drawn By: D.COX

EOG RESOURCES, INC.

LOCATION LAYOUT FOR

SOUTH CHAPITA #6-3
SECTION 3, T10S, R23E, S.L.B.&M.
2105' FNL 2021' FEL



C-0.1'
El. 396.9'

F-11.4'
El. 385.4'

Sta. 3+25

NOTE:
Flare Pit is to
be located a min.
of 100' from the
Well Head.

Approx.
Top of
Cut Slope

Approx.
Toe of
Fill Slope

Handwritten signature

Pit Topsoil
FLARE PIT
20' WIDE BENCH
46'

C-1.8'
El. 398.6'

F-1.3'
El. 395.5'

CATWALK

PIPE RACKS

Round Corners
as needed

C-0.7'
El. 397.5'

Sta. 1+50

El. 400.1'
C-15.3'
(blm. pit)

20' WIDE BENCH
46'

C-1.8'
El. 398.6'

C-1.3'
El. 398.1'

RIG DOG HOUSE

135'

F-1.4'
El. 395.4'

Sta. 0+00

Pit Capacity
With 2' of
Freeboard is
± 12,250 Bbls.

15' WIDE BENCH

RESERVE PITS
(12' Deep)

SLOPE = 1-1/2 : 1

MUD TANKS

PUMP
MUD SHED
HOPPER
POWER
TOOLS
FUEL

WATER

TRAILER
TOILET
FUEL

STORAGE TANK

Topsoil Stockpile

Reserve Pit Backfill
& Spoils Stockpile

Sta. 0+18

TRASH

150'

C-2.1'
El. 398.9'

Proposed Access
Road

2

F-1.8'
El. 395.0'

El. 403.1'
C-18.3'
(blm. pit)

20' WIDE BENCH

C-3.4'
El. 400.2'

4

Elev. Ungraded Ground at Location Stake = 5397.5'
Elev. Graded Ground at Location Stake = 5396.8'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017

EOG RESOURCES, INC.

TYPICAL CROSS SECTIONS FOR

SOUTH CHAPITA #6-3


SECTION 3, T10S, R23E, S.L.B.&M.

2105' FNL 2021' FEL

1" = 20'
X-Section
Scale
1" = 50'

DATE: 07-25-03

Drawn By: D.COX




APPROXIMATE YARDAGES

(6") Topsoil Stripping	=	1,430 Cu. Yds.
Remaining Location	=	5,660 Cu. Yds.
TOTAL CUT	=	7,090 CU.YDS.
FILL	=	3,800 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	=	3,090 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	3,090 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	=	0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017



LEGEND:

⊙ PROPOSED LOCATION



EOG RESOURCES, INC.

SOUTH CHAPITA #6-3
SECTION 3, T10S, R23E, S.L.B.&M.
2105' FNL 2021' FEL




Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

7 22 03
 MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: K.G. REVISED: 00-00-00

A
TOPO



LEGEND:

----- PROPOSED ACCESS ROAD
 _____ EXISTING ROAD

EOG RESOURCES, INC.

**SOUTH CHAPITA #6-3
 SECTION 3, T10S, R23E, S.L.B.&M.
 2105' FNL 2021' FEL**




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
 MAP**

7 22 03
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: K.G. REVISED: 00-00-00

**B
 TOPO**



LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

EOG RESOURCES, INC.

SOUTH CHAPITA #6-3
SECTION 3, T10S, R23E, S.L.B.&M.
2105' FNL 2021' FEL



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813




TOPOGRAPHIC
MAP

7 22 03
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: K.G. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 197' +/-

LEGEND:

- EXISTING PIPELINE
- - - PROPOSED PIPELINE
- - - PROPOSED ACCESS



EOG RESOURCES, INC.

SOUTH CHAPITA #6-3
SECTION 3, T10S, R23E, S.L.B.&M.
2105' FNL 2021' FEL



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

7 22 03
 MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: K.G. REVISED: 00-00-00

D
TOPO

003

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 09/19/2003

API NO. ASSIGNED: 43-047-35217

WELL NAME: S CHAPITA 6-3

OPERATOR: EOG RESOURCES INC (N9550)

CONTACT: ED TROTTER

PHONE NUMBER: 435-789-4120

PROPOSED LOCATION:

SWNE 03 100S 230E

SURFACE: 2105 FNL 2021 FEL

BOTTOM: 2105 FNL 2021 FEL

UINTAH

NATURAL BUTTES (630)

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-80613

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: PRRV

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LATITUDE: 39.97957

LONGITUDE: 109.31029

RECEIVED AND/OR REVIEWED:

- ☒ Plat
- ☒ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. NM 2308)
- ☒ Potash (Y/N)
- ☒ Oil Shale 190-5 (B) or 190-3 or 190-13
- ☒ Water Permit
(No. 49-1501)
- ☒ RDCC Review (Y/N)
(Date:)
- ☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

R649-2-3.

Unit

R649-3-2. General

Siting: 460' From Qtr/Qtr & 920' Between Wells

R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 179-9

Eff Date: 12-28-1999


Siting: 460' from ext boundary & 920' from other wells.

R649-3-11. Directional Drill

COMMENTS:

STIPULATIONS:

1- federal approval



OPERATOR: EOG RESOURCES INC (N9550)

SEC. 3 T.10S, R.23E

FIELD: NATURAL BUTTES (630)

COUNTY: UTAH

CAUSE: 179-9 / 12-28-1999

Wells


- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Field Status

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED



Utah Oil Gas and Mining



PREPARED BY: DIANA MASON
DATE: 24-SEPTEMBER-2003



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

1594 West North Temple, Suite 1210
PO Box 145801
Salt Lake City, Utah 84114-5801
(801) 538-5340 telephone
(801) 359-3940 fax
(801) 538-7223 TTY
www.nr.utah.gov

Michael O. Leavitt
Governor
Robert L. Morgan
Executive Director
Lowell P. Braxton
Division Director

September 25, 2003

EOG Resources, Inc.
P O Box 1910
Vernal, UT 84078

Re: South Chapita 6-3 Well, 2105' FNL, 2021' FEL, SW NE, Sec. 3, T. 10 South, R. 23 East,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-35217.

Sincerely,

John R. Baza
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: EOG Resources, Inc.
Well Name & Number South Chapita 6-3
API Number: 43-047-35217
Lease: UTU-80613

Location: SW NE Sec. 3 T. 10 South R. 23 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

005

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
EOG RESOURCES, INC.

3. ADDRESS OF OPERATOR:
P.O. BOX 1910 CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:
(435) 789-4120

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2105' FNL, 2021' FEL

COUNTY: UINTAH

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 3 10S 23E S

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTU-80613

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
SOUTH CHAPITA 6-3

9. API NUMBER:
4304735217

10. FIELD AND POOL, OR WILDCAT:
NATURAL BUTTES

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Attached documents reflect changes in the casing, cement, and drilling program for the subject well.

Accepted by the
Utah Division of
Oil, Gas and Mining

RECEIVED FOR RECORD ONLY
JAN 14 2004

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Ed Trotter

TITLE Agent

SIGNATURE

DATE 1/9/2004

(This space for State use only)

EIGHT POINT PLAN
SOUTH CHAPITA 6-03
SW/NE, SEC. 3, T10S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	DEPTH (KB)
Green River	1,645'
Wasatch	4,190'
Island	6,615'
KMV Price River	6,785'
KMV Price River Middle	7,205'
KMV Price River Lower	7,775'
Bit Trip Sego	8,165'
Sego	8,225'

EST. TD: 8325

Anticipated BHP 3600 PSI

- 3. PRESSURE CONTROL EQUIPMENT:** Intermediate Hole - 3000 PSIG
 Production Hole – 5000 PSIG
 BOP Schematic Diagrams attached.

4. CASING PROGRAM:

<u>7. CASING PROGRAM:</u>							<u>RATING FACTOR</u>		
<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>LENGTH</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>THREAD</u>	<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
<u>Option 1</u>									
17 ½"	0' – 250'	250'	13 3/8"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
12 1/4"	250' – 2500'+/- KB	2500' +/-	9 5/8"	36.0 #	J-55	ST&C	2020 PSI	3520 PSI	394,000#
7 7/8"	2500' – TD +/-KB	8325' +/-	4 1/2"	11.6 #	N-80	LT&C	6350 PSI	7780 PSI	223,000#
<u>Option 2</u>									
12 1/4"	0' – 2500'+/- KB	2500' +/-	9 5/8"	36.0 #	J-55	ST&C	2020 PSI	3520 PSI	394,000#
7 7/8"	2500' – TD +/-KB	8325' +/-	4 1/2"	11.6 #	N-80	LT&C	6350 PSI	7780 PSI	223,000#

Note: The 12 1/4" hole will be drilled to a total depth of 250' below the base of the Green River lost circulation zone and 9 5/8" casing will be set to that depth. Actual setting depth of the 9 5/8" casing may be less than 2500' in this well.

All casing will be new or inspected.

5. Float Equipment:

Surface Hole Procedure (0-250' Below GL):

Guide Shoe

Insert Baffle

Wooden wiper plug

Centralizers: 1 – 5-10' above shoe, every collar for next 3 joints (4 total).

EIGHT POINT PLAN

SOUTH CHAPITA 6-03 SW/NE, SEC. 3, T10S, R23E, S.L.B.&M. UINTAH COUNTY, UTAH

Float Equipment (Continued)

Intermediate Hole Procedure (250'-2500'):

Guide Shoe

Insert Float Collar (PDC drillable)

Cents.: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2500'-TD):

FS, 1 joint of casing, FC, and balance of casing to surface. Run 11.6#, N-80 burst rating or equivalent marker collars or short casing joints at $\pm 6,785'$ (**Top of Price River**) and $\pm 3,800'$ (**400' above the Wasatch**) (alter depth if needed to avoid placing across any potentially- productive intervals). Centralize 5' above shoe on joint #1, top of joint #2, then every 2nd joint to **400' above Island top** (50 total). Thread lock FS, top and bottom of FC, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (0-250' below GL):

Air – Air Water Mist

Intermediate Hole Procedure (250-2500'):

Water (circulate through reserve pit) with Gel/LCM sweeps.

Production Hole Procedure (2500'-TD):

2700' - 4500' Water (circulate through reserve pit) with Gel/LCM sweeps.

4500' - 6900' Close in mud system. "Mud up" with **6.0 ppb** Diammonium Phosphate (DAP). Drill with DAP water, POLYPLUS for viscosity and hole cleaning, adding KLA-GARD B for supplemental inhibition. Also sweep hole periodically w/ Durogel / LCM sweeps to clean the hole and seal loss zones. Add additional LCM as hole dictates. Mud weight and vis as needed, water loss – no control.

6900' - TD Discontinue KLA-GARD B. Utilize POLYPAC-R for fluid loss control. Maintain **5.5 ppb** DAP. **Do not mix caustic or lime.** Maintain 7.5-8.5 pH. Weight up system and add vis as hole conditions require. Run LCM sweep periodically to seal off loss zones or more often as hole dictates. Water loss: 20 cc's maximum. Expect increasing gas shows requiring heavier mud weights from top of Island onward. Treat CO₂ contamination with DESCO CF and OSIL (Oxygen scavenger) if mud properties dictate.

EIGHT POINT PLAN
SOUTH CHAPITA 6-03
SW/NE, SEC. 3, T10S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

7. VARIANCE REQUESTS:

- A. EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line (Where possible, a straight run blooie line will be used).
- B. EOG Resources, Inc. requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line. (Not required on aerated water system).
- C. EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be 75' in length.

8. EVALUATION PROGRAM:

Logs: RST (reservoir saturation tool) cased hole logs will be run from TD to surface.

9. CEMENT PROGRAM:

Surface Hole Procedure (0-250' Below GL)

Lead: 300 sks (100% excess volume) Class 'G' cement with 2% S1 (CaCl₂) & 0.25 pps D29 (cellophane flakes), mixed at 15.8 ppg, 1.16 ft³/sk., 4.95 gps water.

Top Out: Top out with Class 'G' cement with 2% S1 (CaCl₂) in mix water, 15.8 ppg, 1.16 ft³/sk., 4.95 gps via 1" tubing set at 25' if needed.

Intermediate Hole Procedure (250'-2500')

Option 1:

Lead: 85 sks: (50% excess volume) Class 'G' lead cement (coverage from 1700-1000') with 5% D44 (Salt), 12% D20 (Bentonite), 1% D79% (Extender), 0.25% D112 (Fluid Loss Additive), 0.2% D46 (Anti-Foamer) & 0.25 pps D29 (Cellophane flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 290 sks: (50% excess volume) Class 'G' cement (coverage from 2700-1700') with 10% D53 (Gypsum), 2% S1 (CaCl₂) & 0.25 pps D29 (Cellophane flakes) mixed at 14.2 ppg, 1.61 ft³/sk., 7.9 gps water.

Option 2:

Lead: 210 sks: (60% excess volume) Class 'G' lead cement (coverage from 2300-1800') with 2% BWOC (Calcium Chloride), 1/4#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Tail: 720 sks: (60% excess volume) Class 'G' cement (coverage from 1800'-Surface) with 2% BWOC (Calcium Chloride), 1/4#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

EIGHT POINT PLAN

SOUTH CHAPITA 6-03 **SW/NE, SEC. 3, T10S, R23E, S.L.B.&M.** **UINTAH COUNTY, UTAH**

CEMENT PROGRAM (Continued):

Production Hole Procedure (2500' to TD)

Lead: 110 sks 35:65 Poz G w/ 4% D20 (Bentonite), 2% D174 (Extender), 0.2% D65 (Dispersant), 0.2% D46 (Antifoam), 0.75% D112 (Fluid Loss Additive), 0.15% D13 (Retarder), 0.25 pps D29 (cello flakes), mixed at 13.0 ppg, 1.73 cu. ft./sk., 9.06 gps water

Tail: 190 sks 50:50 Poz G w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.15% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 cu. ft./sk., 5.9 gps water.

10. ABNORMAL CONDITIONS:

INTERMEDIATE HOLE (250-2500')

Potential Problems: Lost circulation below 1800' and minor amounts of gas may be present.

PRODUCTION HOLE (2500'-TD)

Potential Problems: Sloughing shales and key seat development are possible in the Wasatch Formation. CO₂ contamination in the mud is possible in the Price River (Mesa Verde).

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

3000 PSIG DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 3000 PSIG RATED.
CASING FLANGE IS 11" 3000 PSIG RATED.
BOPE 11" 3000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 3000 psig.
3. Annular preventor will be tested to 50% of working pressure, 1500 psig.
4. Casing will be tested to 0.22 psi/ft. or 1500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure-tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 3000 psig BOPE specifications.




5000 PSIG DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 5000 PSIG RATED.
CASING FLANGE IS 11" 5000 PSIG RATED.
BOPE 11" 5000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 5000 psig.
3. Annular preventor will be tested to 50% of working pressure, 2500 psig.
4. Casing will be tested to 0.22 psi/ft. or 2500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure-tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 5000 psig BOPE specifications.



UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. TYPE OF WORK ☒ DRILL ☐ REENTER

b. TYPE OF WELL ☐ Oil Well ☒ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

2. Name of Operator

EOG RESOURCES, INC.

3a. Address

P.O. BOX 1910, VERNAL, UT 84078

3b. Telephone Number: (435)789-4120

4. Location of Well (Report location clearly and in accordance with any State requirements. *)
At surface

2105' FNL & 2021' FEL

SW/NE

At proposed prod. Zone

14. Distance in miles and direction from nearest town or post office*

28.25 MILES SOUTHEAST OF OURAY, UTAH

15. Distance from proposed location to nearest property or lease line, ft.
(Also to nearest drig. Unit line, if any)

2021'

16. No. of acres in lease

642

18. Distance from proposed location* to nearest well, drilling, completed, or applied for, on this lease, ft.

See Map C

19. Proposed depth

8325'

21. Elevations (show whether DF, KDB, RT, GL, etc.)

5396.8 FEET GRADED GROUND

22. Approx. date work will start*

UPON APPROVAL

5. Lease serial No.

UTU-80613

6. If Indian, Allottee or Tribe name

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.

SOUTH CHAPITA 6-3

9. API Well No.

43-047-35217

10. Field and pool, or Exploratory
NATURAL BUTTES

11. Sec., T., R., M., or BLK. And survey of area

SEC. 3, T10S, R23E, S.L.B.&M.

12. County or parish

UINTAH

13. State

UTAH

17. Spacing Unit dedicated to this well

20. BLM/BIA Bond No. on file
#NM 2308

23. Estimated duration

RECEIVED

JAN 22 2004

DIV. OF OIL, GAS & MINING

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan
3. A Surface Use Plan (if the location is on National Forest System lands, the SUPO shall be filed with the appropriate Forest Service Office.

4. Bond to cover the operations unless covered by an existing bond on file (see item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the Authorized officer.

25. Signature

Ed Trotter

Name (Printed/ Typed)

Ed Trotter

Date

September 5, 2003

Title

Agent

Approved by (Signature)

Edwin I. Ferman

Name (Printed/ Typed)

EDWIN I FERMAN

Date

1/13/04

Title

Office

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

UDD06M

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: EOG Resources, Inc.

Well Name & Number: South Chapita 6-3

Lease Number: U-80613

API Number: 43-047-35217

Location: SWNE Sec. 3 T.10S R. 23E

Agreement: N/A

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to John Mayers of this office **prior to setting the next casing string or requesting plugging orders**. Faxed copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a **3M** system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint. Surface casing setting depths are based on ground level elevations only.

All casing strings below the conductor shall be pressure tested to 0.22 psi/ft of casing string length or 1500 psi, whichever is greater but not to exceed 70% of the minimum internal yield.

The base of the usable water has been identified as $\pm 3295'$. The usable water must be isolated by either setting the intermediate casing at $\pm 3345'$ or bringing the cement behind the production casing up to at least $\pm 3095'$.

If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

A cement bond log (CBL) will be run from the production casing shoe to top of the cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after

completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

Please submit to this office, in LAS format, an electronic copy of all logs run on this well. This submission will replace the requirement for submittal of paper logs to the BLM.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Written notification of such must be submitted to this office not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas

can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5(d) shall be submitted to the appropriate Field Office within 60 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (1).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergencies, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries and tested for meter accuracy at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires

that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, you must contact one of the following individuals:

Ed Forsman (435) 828-7874
Petroleum Engineer

Kirk Fleetwood (435) 828-7875
Petroleum Engineer

BLM FAX Machine (435) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spend solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Resources Inc..

API Number: 43-047-35217

Well Name & Number: SC 6-3

Lease number: U-80613

Location: SW NE Sec, 3, T.10S. R. 23E.

Surface Ownership: BLM

Date NOS Received: 8/22/03

Date APD Received: 9/27/03

Conditions for Approval are in the APD

DIVISION OF OIL, GAS AND MINING**SPUDDING INFORMATION**Name of Company: EOG RESOURCES INCWell Name: S CHAPITA 6-3Api No: 43-047-35217 Lease Type: FEDERALSection 03 Township 10S Range 23E County UINTAHDrilling Contractor BILL MARTIN'S RIG # AIR**SPUDDED:**Date 02/11/04Time 3:00 PMHow ROTARY**Drilling will commence:** _____Reported by ED TROTTERTelephone # 1-435-789-4120Date 02/12/2004 Signed CHD

009

(3/89)

STATE OF UTAH
STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

OPERATOR: EOG Resources, Inc.
ADDRESS: P.O. BOX 250
BIG PINEY, WYOMING 83113

OPERATOR ACCT. NO. N 9550
OPERATOR ACCT. NO. N
FAX: EARLENE RUSSELL
(801) 359-3940

ENTITY ACTION FORM - FORM 6

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	LOCATION				COUNTY	SPUD DATE	EFFECTIVE DATE
					QQ	SEC.	TP	RG			
A	99999	14057	43-047-35217	SOUTH CHAPITA 6-3	SW/NE	3	10S	23E	UINTAH	2/11/2004	2/19/04
1 COMMENTS: PRRV											
2 COMMENTS:											
3 COMMENTS:											
4 COMMENTS:											
5 COMMENTS:											

ACTIONS CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

Signature
Regulatory Analyst 7/29/2001
Title Date
Phone No. (307) 276-4842

RECEIVED

FEB 13 2004

DIV. OF OIL, GAS & MINING

T-616 P.01/01 F-180

3072763335

From:EOG - BIG PINEY, WY.

Feb-13-04 11:26am

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

011

SUNDRY NOTICES AND REPORTS ON WELLS
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.***SUBMIT IN TRIPLICATE - Other instructions on reverse side.**

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. UTU 80613
2. Name of Operator EOG RESOURCES, INC		6. If Indian, Allottee or Tribe Name
3a. Address P. O. BOX 250 BIG PINEY, WY 83113		7. If Unit or CA/Agreement, Name and/or No.
3b. Phone No. (include area code) Ph: 307.276.4833		8. Well Name and No. SOUTH CHAPITA 6-3
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Sec 3 T10S R23E SWNE 2105FNL 2021FEL 39.97946 N Lat, 109.31018 W Lon		9. API Well No. 43-047-35217
		10. Field and Pool, or Exploratory NATURAL BUTTES
		11. County or Parish, and State UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc requests authorization for disposal of produced water from the referenced well to any of the following locations.

1. Natural Buttes Unit 21-20B SWD.
2. Ace Disposal.
3. EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecraft Unit).
4. RN Industries.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

14. I hereby certify that the foregoing is true and correct. Electronic Submission #27872 verified by the BLM Well Information System For EOG RESOURCES, INC, sent to the Vernal	
Name (Printed/Typed) ALFREDA SCHULZ	Title AUTHORIZED REPRESENTATIVE
Signature (Electronic Submission)	Date 02/13/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____	Title _____	Date _____
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		
Office _____		

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED****RECEIVED****FEB 17 2004**

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

008

SUNDRY NOTICES AND REPORTS ON WELLS
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.***SUBMIT IN TRIPLICATE - Other instructions on reverse side.**

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. UTU - 80613
2. Name of Operator EOG RESOURCES, INC		6. If Indian, Allottee or Tribe Name
3a. Address P. O. BOX 250 BIG PINEY, WY 83113		7. If Unit or CA/Agreement, Name and/or No.
3b. Phone No. (include area code) Ph: 307.276.4833		8. Well Name and No. SOUTH CHAPITA 6-3
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Sec 3 T10S R23E SWNE 2105FNL 2021FEL 39.97946 N Lat, 109.31018 W Lon		9. API Well No. 43-047-35217
		10. Field and Pool, or Exploratory NATURAL BUTTES
		11. County or Parish, and State UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	Well Spud
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc spud a 20" surface hole at the referenced location 2/11/04 at 3:00 p.m. The contractor was Bill Jr's Air Rig. Ed Trotter, representative for EOG, notified Ed Forsman of the Vernal BLM office and Carol Daniels of the Utah Division of Oil, Gas & Mining of the spud 2/11/04.

14. I hereby certify that the foregoing is true and correct.

**Electronic Submission #27871 verified by the BLM Well Information System
For EOG RESOURCES, INC, sent to the Vernal**

Name (Printed/Typed) ALFREDA SCHULZ

Title SR. REGULATORY ASSISTANT

Signature (Electronic Submission)

Date 02/13/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ******FEB 17 2004**

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: November 30, 2000

010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
UTU-80613

1a. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other			6. If Indian, Allottee or Tribe Name		
b. Type of Completion <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr. Other _____			7. Unit or CA Agreement Name and No.		
2. Name of Operator EOG RESOURCES, INC			Contact: ALFREDA SCHULZ E-Mail: alfreda_schulz@eogresources.com		
3. Address P. O. BOX 250 BIG PINEY, WY 83113			3a. Phone No. (include area code) Ph: 307.276.4833		
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface SWNE 2105FNL 2021FEL 39.97957 N Lat, 109.31029 W Lon At top prod interval reported below SWNE 2105FNL 2021FEL 39.97957 N Lat, 109.31029 W Lon At total depth SWNE 2105FNL 2021FEL 39.97957 N Lat, 109.31029 W Lon			8. Lease Name and Well No. SOUTH CHAPITA 6-83		
14. Date Spudded 02/11/2004			15. Date T.D. Reached 03/05/2004		
16. Date Completed <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod. 03/19/2004			9. API Well No. 43-047-35217		
18. Total Depth: MD 8272 TVD			19. Plug Back T.D.: MD 8264 TVD		
20. Depth Bridge Plug Set: MD TVD			10. Field and Pool, or Exploratory NATURAL BUTTES/MESAVERDE		
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) (RST, CBL-GR/CCU)			11. Sec., T., R., M., or Block and Survey or Area Sec 3 T10S R23E Mer SLB		
22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Directional Survey? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis)			12. County or Parish UINTAH		
			13. State UT		
			17. Elevations (DF, KB, RT, GL)* 5415 KB		

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12.250	9.625 J55	36.0	0	1738		700			
7.875	4.500 N80	11.6	0	8325		1200			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	8272							

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) MESAVERDE	7382	8217	8109 TO 8217			3 SPF/PRODUCING
B)			7882 TO 8003			3 SPF/PRODUCING
C)			7706 TO 7832			2 SPF/PRODUCING
D)			7553 TO 7663			3 SPF/PRODUCING

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
8109 TO 8217	1190 BBLs GELLED WATER & 168,546# 20/40 SAND
7882 TO 8003	1197 BBLs GELLED WATER & 169,900# 20/40 SAND
7706 TO 7832	1185 BBLs GELLED WATER & 167,472# 20/40 SAND
7553 TO 7663	1245 BBLs GELLED WATER & 168,026# 20/40 SAND

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
03/19/2004	04/08/2004	24	→	12.0	498.0	95.0			FLOWES FROM WELL
Choke Size	Tbg. Press. Flwg. 1230 SI	Csg. Press. 1690.0	24 Hr. Rate →	Oil BBL 0	Gas MCF 498	Water BBL 95	Gas:Oil Ratio	Well Status PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #29471 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

RECEIVED

APR 15 2004

DIV. OF OIL, GAS & MINING

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Sold, used for fuel, vented, etc.)
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top Meas. Depth
MESAVERDE	7382	8217		WASATCH NORTH HORN ISLAND MESAVERDE BUG TOP KMV-MIDDLE PRICE RIVER KMV-LOWER PRICE RIVER	4179 6013 6331 6600 7125 7744

32. Additional remarks (include plugging procedure):

FLOWING THROUGH QUESTAR SALES METER # 5990. TWO (2) 400 BBL TANKS ON LOCATION # 80192V, 80193V.
Perforated the Lower Price River from 8109-11', 8117-18', 8135-37', 8167-68', 8187-89', 8200-8201' & 8216-17' @ 3 SPF.
Perforated the Lower Price River from 7882-84', 7911-14', 7927-28', 7975-77' & 8001-03' @ 3 SPF.
Perforated the Lower/Middle Price River from 7706-08', 7725-26', 7752-53', 7774-76', 7800-01', 7807-08' & 7830-32' @ 2 SPF.

33. Circle enclosed attachments:

- | | | | |
|---|--------------------|---------------|-----------------------|
| 1. Electrical/Mechanical Logs (1 full set req'd.) | 2. Geologic Report | 3. DST Report | 4. Directional Survey |
| 5. Sundry Notice for plugging and cement verification | 6. Core Analysis | 7 Other: | |

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

Electronic Submission #29471 Verified by the BLM Well Information System.
For EOG RESOURCES, INC, sent to the Vernal

Name (please print) ALFREDA SCHULZ

Title SR. REGULATORY ASSISTANT

Signature (Electronic Submission)

Date 04/12/2004

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ****

Additional data for transaction #29471 that would not fit on the form

26. Perforation Record, continued

Perf Interval	Size	No. Holes	Perf Status
7382 TO 7501			3 SPF/PRODUCING

27. Acid, Fracture, Treatment, Cement Squeeze, etc., continued

Depth Interval	Amount and Type of Material
7382 TO 7501	1216 BBLS GELLED WATER & 174,385# 20/40 SAND

32. Additional remarks, continued

Perforated the Middle Price River from 7553-54', 7572-75', 7598-99', 7624-25', 7644-46' & 7661-63' @ 3 SPF.
Perforated the Middle Price River from 7382-84', 7393-95', 7458-59', 7469-70', 7482-84' & 7499-7501' @ 3 SPF.

012

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 80613
2. NAME OF OPERATOR: EOG RESOURCES, INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: P.O. BOX 250 CITY BIG PINEY STATE WY ZIP 83113		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: SWNE 2105 FNL 2021 FEL 39.97957 LAT 109.31029 LON		8. WELL NAME and NUMBER: SOUTH CHAPITA 6-03
PHONE NUMBER: (307) 276-3331		9. API NUMBER: 4304735217
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 3 10S 23E S		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES / MESAVERDE
COUNTY: UTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: CONTINUED COMPLETION
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. continued completion in the Mesaverde formation of the referenced well as follows:

- Set 10k composite bridge plug @ 7360'. Perforated the Lower Price River from 7165-67', 7183-86', 7233-34', 7270-73' & 7300-01' w/2 SPF. Fracture stimulated with 956 bbls gelled water & 108,856 # 20/40 sand.
- Set 10k composite frac plug @ 7141'. Perforated the Middle Price River from 6970-73', 7004-06', 7035-37', 7073-75', 7098-7100' & 7110-11' w/2 SPF. Fracture stimulated with 1189 bbls gelled water & 169,775 # 20/40 sand.
- Set 10k composite frac plug @ 6936'. Perforated the Middle Price River from 6685-87', 6764-66', 6790-92', 6830-33' & 6884-86', w/2 SPF. Fracture stimulated with 1485 bbls gelled water & 239,433 # 20/40 sand.
- Set 10k composite frac plug @ 6616'. Perforated the Upper Price River from 6359-63', 6408-10', 6509-12' & 6583-86' w/2 SPF. Fracture stimulated with 1337 bbls gelled water & 205,994 # 20/40 sand. Drilled out composite frac plugs @ 6616', 6936' & 7141'. Landed tubing @ 6324'.

Returned to sales 11/10/2004 through Questar meter # 5990

TEST: 472 MCFD, 8 BC & 162 BW on 12/64" choke in 24 hours. FTP 1500 & CP 1850 psig.

RECEIVED

NOV 18 2004

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Kaylene R. Gardner

TITLE Regulatory Assistant

SIGNATURE

DATE 11/16/2004

(This space for State use only)



EOG Resources, Inc.
 600 Seventeenth Street
 Suite 1100N
 Denver, CO 80202
 (303) 572-9000
 Fax: (303) 824-5400

February 3, 2005

Utah Division of Oil, Gas, & Mining
 1594 West North Temple.
 Vernal, UT 84078

RECEIVED

FEB 09 2005

DIV. OF OIL, GAS & MINING

RE: S. Chapita 1-03
T10S-R23E-Sec. 03
S. Chapita 6-03 and
S. Chapita 8-03
T10S-R23E-Sec. 03 and
 Uintah County, Utah

43-047-35217

Ms. Carol Daniels:

Enclosed herewith are the following logs and data associated with the subject well:

S. Chapita 1-03

Repeat Formation Tester 01-12-04 (1)
 Array Induction W/Linear Correlation GR 01-11-04 (1)
 Compensated Neutron Three Detector Lithodensity GR 01-11-04 (1)
 Microlog 01-11-04 (1)

✓ S. Chapita 6-03

✓ Cement Bond Log Gammy Ray/CCL 03-09-04 (1)
 ✓ RST Log Gamma Ray Collars 03-09-04 (1)
 ✓ Compensated Neutron Casing Collar Locator GR 03-09-047 (1)

S. Chapita 8-03

Cement Bond Log Gammy Ray/CCL 03-20-04 (1)
 RST Log Gamma Ray Collars 03-20-04 (1)

If you have any questions, please do not hesitate to contact me.

Very truly yours,

EOG RESOURCES, INC.

Delores Montoya

Delores Montoya
 Exploration & Operations Secretary
 Denver Office

Enc.8

cc: Well File

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. UTU-80613
2. Name of Operator EOG Resources, Inc.		6. If Indian, Allottee or Tribe Name
3a. Address 600 17th St., Suite 1000N, Denver, CO 80202	3b. Phone No. (include area code) 303-824-5526	7. If Unit or CA/Agreement, Name and/or No.
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) SWNE, SECTION 3, T10S, R23E 2105 FNL, 2021 FEL, 39.97957 LAT, 109.31029 LON		8. Well Name and No. South Chapita 6-03
		9. API Well No. 43-047-35217
		10. Field and Pool, or Exploratory Area Natural Buttes
		11. County or Parish, State Uintah County, Utah

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Pit reclamation
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The reserve pit for the referenced location was closed on 12/08/2005 as per the APD procedure.

EOG Resources, Inc. operates under Nationwide Bond #2308.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

14. I hereby certify that the foregoing is true and correct Name (Printed/Typed) Mary Maestas		Title Operations Clerk
Signature 		Date 04/26/2006


THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by _____	Title _____	Date _____
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office _____	

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

MAY 01 2006

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-80613			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: EOG Resources, Inc.		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078		8. WELL NAME and NUMBER: S CHAPITA 6-3			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2105 FNL 2021 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 03 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047352170000			
PHONE NUMBER: 435 781-9111 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: UINTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 2/8/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: _____ </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: _____
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: _____			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. EOG Resources, Inc. respectfully requests authorization to Recomplete the referenced well as per the attached procedure.					
<div style="text-align: right;"> Accepted by the Utah Division of Oil, Gas and Mining </div>		Date: February 08, 2010 By: 			
NAME (PLEASE PRINT) Mickenzie Gates	PHONE NUMBER 435 781-9145	TITLE Operations Clerk			
SIGNATURE N/A		DATE 2/8/2010			

RECEIVED February 08, 2010



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Sundry Conditions of Approval Well Number 43047352170000

Authorization: Cause No. 179-14.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

Date: February 08, 2010
By: Dan K. Quist

RECOMPLETION PROGRAM

SCW 6-03

SCW 6-03
2105' FNL & 2021' FEL (SW/NE)
Section 3, T10S, R23E
Uintah County, Utah

February 3, 2010
EOG WI: 100%
NRI: 87.5%
API# 43-047-35217
AFE# 310044

WELL DATA:

ELEVATION: 5,397' GL KB: 5,415' (18' KB)
TOTAL DEPTH: 8,325' KB PBD: 8,282' KB (Top of FC)

CASING: 9-5/8", 36# J-55 STC set @ 1,738'. Cemented w/ 130 sx Hi-Lift. Top out w/ 480 sxs cmt in 3 stages. Cement to surface.

4-1/2", 11.6#, N-80 set @ 8,325'. Cemented w/ 200 sx HiLift 35/65 Pozmix "G" & 1,000 sx 50/50 Pozmix "G". Bumped plug, float held. Full Returns. Marker joint @ 6,759' (22'). Cement Top est. @ 1,100'.

EXISTING PERFS	SPF/Phasing	INTERVAL	FRAC #
8109-8111', 8117-8118', 8135-8137', 8167-8168', 8187-8189', 8200-8201', 8216-8217'	3/120°	Lower Price River	1
7882-7884', 7911-7914', 7927-7928', 7975-7977', 8001-8003'	3/120°	Lower Price River	2
7706-7708', 7725-7726', 7752-7753', 7774-7776', 7800-7801', 7807-7808', 7830-7832'	2/180°	Lower Price River	3
7553-7554', 7572-7575', 7598-7599', 7624-7625', 7644-7646', 7661-7663'	3/120°	Lower Price River	4
7382-7384', 7393-7395', 7458-7459', 7469-7470', 7482-7484', 7499-7501'	3/120°	Lower Price River	5
7165-7167', 7183-7186', 7233-7234', 7270-7273', 7300-7301'	2/180°	Middle Price River	6
6970-6973', 7004-7006', 7035-7037', 7073-7075', 7098-7100', 7110-7111'	2/180°	Middle Price River	7
6685-6687', 6764-6766', 6790-6792', 6830-6833', 6884-6886'	2/180°	Middle Price River	8
6359-6363', 6408-6410', 6509-6512', 6583-6586'	2/180°	Upper Price River	9

PROPOSED PERFS	SPF/Phasing	INTERVAL	FRAC #
6094-6095', 6106-6107', 6113-6114', 6158-6159', 6162-6163', 6166-6167', 6205-6206', 6250-6251', 6254-6255', 6261-6262', 6279-6280', 6284-6285', 6288-6289', 6293-6294'	2/180°	Upper Price River	10
5628-5629', 5640-5641', 5696-5697', 5710-5711', 5856-5857', 5868-5869', 5902-5903', 5931-5932', 5979-5980', 5998-5999', 6026-6027', 6029-6030', 6032-6033', 6052-6053'	2/180°	Ba/NH	11
5183-5184', 5189-5190', 5222-5223', 5246-5247', 5268-5270', 5374-5375', 5400-5401', 5426-5427', 5434-5435', 5520-5521', 5544-5545'	2/180°	Ca/Ba	12

**RECOMPLETION PROGRAM
SCW 6-03**

PROCEDURE:

1. MIRUSU. Kill well w/treated water. ND tree. NU 10M psig BOPE. PU 3-7/8" bit, 4-1/2" casing scraper, & 2-3/8" 4.7# N-80 EUE tubing. RIH to PBTD. POH.
2. RUWL. Set 10K CFP @ **6,310'**. RDWL.
3. Test casing & BOPE to **6,500** psig. RUWL. Perforate **Upper Price River** intervals from **6,094'-6,294'** as shown using a 3-1/8" HSC ported casing gun. RDWL.
4. RU Service Company. Frac down casing per attached procedure. RD Service Company.
5. RUWL. Set Weatherford 10K composite frac plug @ **6,070'±**. Perforate **Ba/North Horn** intervals from **5,628'-6,053'** as shown. RDWL.
6. RU Service Company. Frac down casing per attached procedure. RD Service Company.
7. RUWL. Set Weatherford 10K composite frac plug @ **5,570'±**. Perforate **Ca/Ba** intervals from **5,183'-5,545'** as shown. RDWL.
8. RU Service Company. Frac down casing per attached procedure. RD Service Company. Flow back immediately (if required, set a composite bridge plug at **5,140'±**). Following flowback, RIH w/3-7/8" bit & pump off sub. Drill out composite frac plugs. Clean out to PBTD. Land tubing @ **6,200'**. ND BOPE. NU 10M psig tree. Drop ball. Pump off bit & sub. Swab/flow test.
9. RDMOSU. Place well on production.


PREPARED BY:

SHAY HOLTE, COMPLETIONS ENGINEER

APPROVED BY:

PAUL PENDLETON, OPERATIONS MANAGER

RECEIVED February 08, 2010

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-80613			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: EOG Resources, Inc.		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 600 17th Street, Suite 1000 N, Denver, CO, 80202		8. WELL NAME and NUMBER: S CHAPITA 6-3			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2105 FNL 2021 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 03 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047352170000			
PHONE NUMBER: 435 781-9111 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: UINTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 4/5/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Install H2S treater </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Install H2S treater
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Install H2S treater			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. EOG Resources, Inc. requests permission to install an H2S treater on the above-referenced well pad. The proposed treater will be installed on existing disturbance; no new disturbance will be required. Attached is a diagram showing general placement of the facilities.					
Accepted by the Utah Division of Oil, Gas and Mining Date: 02/03/2011 By: 					
NAME (PLEASE PRINT) Mary Maestas	PHONE NUMBER 303 824-5526	TITLE Regulatory Assistant			
SIGNATURE N/A	DATE 1/28/2011				

